



## Commercial Series TA25TC Tagalong Series Pierced Frame

• G.V.W.R. - 50,000 #	• Axles - 3 Dexter 22,500 # dual wheel air brake axles with spring break
• G.A.W.R. (Each Axle) - 22,500 #	• Suspension - Heavy duty Hutch 9700
• Coupler - 3 position pintle ring	• Tires - ST215/75R/17.5" load range H
• Safety Chain - 7/16" grade 70 with hooks	• Wheel - 6.75 x 17.5" 8 bolt Hub-piloted disc
• Jack - 25,000 # Dual 2 speed landing gear	• Deck - 2" oak
• Frame - 14" @ 26 # I-beam	• Lights - L.E.D. stop, tail, turn, and clearance
• Crossmembers - 5" channel on 16" center	• Elec. Plug - 7-way semi type
• Side rails - 8" channel with (10) D-rings	• Paint - high solids acrylic enamel

### Standard Features

### Optional Features

• ABS on two axles	• Paver option
• Spring brakes both axles	• Spare tire mount
• Sealed modular wiring harness	• Ramp lift kit
• Internal to air and emergency relay valve	• Wood-covered ramps
• Oil bath axles	• Anti twist pipe
• 5' dovetail	• 36" Wide Hyd Ramps
• 5' ramps spring loaded	
• Locking tool box	
• Rubber mounted lights	

### Dimensions

Length	A	B	C	D	E	Dove
29'	348"	211.5"	69"	36.75"	102"	60"
33'	396"	235.5"	69"	36.75"	102"	60"

\*Trailer specification subject to change

